

PROJECT: **SITE AND FOUNDATION WORKS**
LOCATION:
DATE:
SUBJECT: **BILL OF QUANTITIES**

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
I.	GENERAL REQUIREMENTS							193,000.00
	Mobilization, Demobilization and Site Preparation	lot	1.00			15,000.00	15,000.00	15,000.00
	EHS Requirements	lot	1.00			30,000.00	30,000.00	30,000.00
	Temporary Facilities (Electricity)	mos	2.00			6,500.00	6,500.00	13,000.00
	Temporary Facilities (Water)	mos	2.00			3,500.00	3,500.00	7,000.00
	Project-In-Charge	mos	2.00			35,000.00	35,000.00	70,000.00
	Safety Officer	mos	2.00			25,000.00	25,000.00	50,000.00
	As Built Plans	lot	1.00			5,000.00	5,000.00	5,000.00
	Rebar Testing (Assistance)	lot	1.00			1,500.00	1,500.00	1,500.00
	Concrete Testing (Assistance)	lot	1.00			1,500.00	1,500.00	1,500.00
II.	SITE WORKS / EARTH WORKS							331,090.00
	Soil Poisoning	sq.m	1,060.00	120.00	50.00		170.00	180,200.00
	Vapor Barrier	sq.m	1,060.00	85.00	34.00		119.00	126,140.00
	Lean Concrete	cu.m	55.00	DSM	450.00		450.00	24,750.00
III.	STRUCTURAL WORKS							2,463,800.00
	Reinforcements							
	Foundation Zone 1 (60%)	kgs	71,190.00	DSM	9.50		9.50	676,305.00
	Foundation Zone 2 (40%)	kgs	47,460.00	DSM	9.50		9.50	450,870.00
	RC Wall Zone 1 (60%)	kgs	12,318.00	DSM	9.50		9.50	117,021.00
	RC Wall Zone 2 (40%)	kgs	8,212.00	DSM	9.50		9.50	78,014.00
	Wall Column Starter Bars Zone 1 (60%)	kgs	2,772.00	DSM	9.50		9.50	26,334.00
	Wall Column Starter Bars Zone 2 (40%)	kgs	1,848.00	DSM	9.50		9.50	17,556.00
	Concreting							
	Foundation (Including Elevator Pit)	cu.m	1,280.00	DSM	450.00		450.00	576,000.00
	Formworks						-	-
	Foundation	sq.m	230.00	DSM	280.00		280.00	64,400.00
	225mm Wide x 6mm THK. PVC, Dumbell Type with Center Bulb	l.m.	340.00	1,200.00	120.00	25.00	1,345.00	457,300.00
TOTAL COST:								2,987,890.00

Prepared by:

JOHN KRISTIAN A. RAMOS
Project Engineer

PROJECT: **TRANSFORMER PAD**

LOCATION:

DATE

SUBJECT: **BILL OF QUANTITIES**

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
								5,003,600.75
I	GENERAL REQUIREMENTS							
	Mobilization/ Demobilization	lot	1.00				-	included in Meter Center
	Site Management	months	2.00				-	included in Meter Center
	Temporary Facilities (Office, Warehouse, Barracks & Etc.)	months	2.00				-	included in Meter Center
	Water and Electricity	months	2.00				-	included in Meter Center
	Safety Requirements (Medical fit to work, NBI or Police, PPE, Barricades & Etc.)	lot	1.00				-	included in Meter Center
	Testing	lot	1.00				-	included in Meter Center
	SUBTOTAL I - GENERAL REQUIREMENTS							-
II	STRUCTURAL WORKS							
	All works shall be in accordance with the Drawings, Specifications and							
	Tender Documents, all to the approval and acceptance of the Designer/Owner							
2.1	Site Works							
2.1.1	Excavation	m3	18.00	included	included	430.00	430.00	7,740.00
2.1.2	Gravel Bedding	m3	6.00	1,300.00	484.79	included	1,784.79	10,708.74
2.1.3	Backfilling & Compaction	m2	15.75	included	included	317.16	317.16	4,995.27
	Sub-total: Site Works							23,444.01
2.2	Concrete							
2.2.1	Column Footing	m3	2.25	5,400.00	870.13	-	6,270.13	14,107.80
2.2.2	Tie Beam	m3	1.32	5,400.00	870.13	-	6,270.13	8,276.58
2.2.3	Column	m3	2.99	5,400.00	870.13	-	6,270.13	18,747.70
2.2.4	Slab	m3	3.95	5,400.00	870.13	-	6,270.13	24,767.03
2.2.5	Beam	m3	1.62	5,400.00	870.13	-	6,270.13	10,157.62
2.2.6	Genset Pad	m3	2.20	5,400.00	870.13	-	6,270.13	13,794.30
			14.33					
	Sub-total: Concrete							89,851.03
2.3	Reinforcing Steel Bars							
2.3.1	Column Footing	kgs	132.72	59.76	8.48	2.77	71.00	9,423.17
2.3.2	Tie Beam	kgs	217.42	59.76	8.48	2.77	71.00	15,436.89
2.3.3	Column	kgs	619.73	59.76	8.48	2.77	71.00	44,001.04
2.3.4	Slab	kgs	296.16	59.76	8.48	2.77	71.00	21,027.46
2.3.5	Beam	kgs	531.43	59.76	8.48	2.77	71.00	37,731.71
2.3.6	Genset Pad	kgs	248.00	59.76	8.48	2.77	71.00	17,608.09
	Sub-total: Rebars							145,228.36
2.4	Formworks							
2.4.1	Column Footing	m2	6.00	350.00	300.00	included	650.00	3,900.00
2.4.2	Tie Beam	m2	12.00	350.00	300.00	included	650.00	7,800.00
2.4.3	Column	m2	48.72	350.00	300.00	included	650.00	31,668.00
2.4.4	Slab	m2	28.50	350.00	300.00	included	650.00	18,525.00
2.4.5	Beam	m2	56.40	350.00	300.00	included	650.00	36,660.00
2.4.6	Genset Pad	m2	2.75	350.00	300.00	included	650.00	1,787.50
	Sub-total: Formworks							100,340.50
	SUBTOTAL II - STRUCTURAL WORKS							358,863.90
III	ARCHITECTURAL WORKS							
3.1	Metal Works							
3.1.1	Cyclone Wire	m2	16.00	3,335.11	667.02		4,002.13	64,034.08
3.1.2	1 1/2" G.I. Pipe Sch.40	lm	35.00	378.67	681.60	236.29	1,296.56	45,379.48
3.1.3	10mm diam x 6m Plain Round Bar	lm	35.00	249.00	74.88		323.88	11,335.80
3.1.4	Consumables	lot	1.00			4,745.00	4,745.00	4,745.00
3.2	Painting Works							
3.2.1	Smooth Latex Paint	m2	136.00	227.66	235.60	included	463.26	63,003.30
3.2.5	Epoxy Primer	m2	54.00	351.11	335.47	included	686.58	37,075.32
3.2.6	Consumables	lot	1.00			6,500.00	6,500.00	6,500.00
3.3	Waterproofing Works							
3.3.1	Trafficable Liquid Applied Membrane	m2	30.00	739.89	432.74	included	1,172.63	35,178.87
	SUBTOTAL III - ARCHITECTURAL WORKS							267,251.85
IV	ELECTRICAL WORKS							
3.1	Conduits and Fittings							
3.1.1	Cable Ladder							
	Angle Bar 1 1/2" x 1 1/2" x 4mm	lm	12.00	946.40	429.93		1,376.33	16,515.96

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
	Flat Bar 1" x 4mm	lm	5.00	345.80	188.96		534.76	2,673.80
3.2	Wires and Cables							
3.2.1	200mm² THW Wire	lm	225.00	1,457.25	455.86	31.91	1,945.02	437,629.38
	100mm² THW Wire	lm	75.00	677.22	184.01	22.16	883.39	66,254.42
3.3	Others							
3.3.1	C - Channel 6" x 2" x 1/4" - 6m	pcs	2.00	5,850.00	1,462.50		7,312.50	14,625.00
3.3.2	Machine Bolt, 5/8" x 500mm	pcs	4.00	585.00	100.00		685.00	2,740.00
3.3.3	Ground Rod, Copper 20mm diam x 3m	pcs	1.00	2,463.50	1,126.82		3,590.32	3,590.32
3.3.4	30mm2 Bare Copper Wire	m	7.00	329.46	68.94	7.79	406.19	2,843.31
3.3.5	Consumables	lot	1.00	13,000.00	8,667.88		21,667.88	21,667.88
3.3.6	Oil Trap							
	12mm Ø x 6m	kgs	85.28	43.14	22.49	1.87	67.50	5,756.65
	Concrete (3000 psi)	m3	1.19	5,165.00	870.13	-	6,035.13	7,181.81
	Forms	m2	7.20	309.92	116.88	21.34	448.14	3,226.61
	4" diam G.I. Pipe	lm	1.00	10,400.00	1,000.00		11,400.00	11,400.00
3.4	GENSET WORKS							
3.4.1	Placement of genset	lot	1.00	-	-	29,200.00	29,200.00	29,200.00
3.4.2	Wires and Cables						-	-
	125mm.sq THW Cu.Wire (Genset to EDP)	lm	215.00	866.25	238.78	26.86	1,131.89	243,355.87
	125mm.sq Fire Rated Cu.Wire (Genset to Fire Pump)	lm	649.00	2,139.06	238.78	26.86	2,404.70	1,560,649.48
	125mm.sq THW Cu.Wire (Genset to Domestic Cistern)	lm	564.00	868.45	238.78	26.86	1,134.09	639,625.50
	100mm.sq THW Cu.Wire (Genset to EPP-GEN Bldg A)	lm	346.00	677.22	677.22	22.16	1,376.59	476,300.96
	80mm.sq THW Cu.Wire (Genset to Open Space)	lm	357.00	551.32	174.41	18.07	743.80	265,538.06
	30mm.sq THW Cu.Wire (Genset to EDP Ground)	lm	72.00	221.57	62.69	7.79	292.05	21,027.65
3.4.3	Roughing-ins							
	110mm diam PVC Pipe	lm	44.00	1,239.81	329.03	22.88	1,591.72	70,035.68
	90mm diam PVC Pipe	lm	13.00	953.70	286.11	19.07	1,258.88	16,365.44
	63mm diam PVC Pipe	lm	13.00	320.00	70.79	3.80	394.59	5,129.67
	80mm diam RSC Pipe	lm	1.00	4,199.80	840.61	188.92	5,229.33	5,229.33
3.4.3	Panelboard MCR 1600AT/2000AE 3P ACB 80 kAic Nema 3P	set	1.00	203,034.00	40,606.80	3,045.51	246,686.31	246,686.31
3.4.4	Accessories						-	-
	Ground Rod, Copperweld, 20mm diam x 3m	pcs	1.00	2,463.50	1,126.82		3,590.32	3,590.32
	30mm.sq Bare Copper Wire	lm	7.00	329.46	68.94	7.79	406.19	2,843.31
	Consumables	lot	1.00	19,500.00	17,335.75		36,835.75	36,835.75
3.4.5	Service Entrance Post							
	10mm Ø x 6m	kgs	100.00	43.14	22.49	1.87	67.50	6,750.29
	12mm Ø x 9m	kgs	96.00	43.14	22.49	1.87	67.50	6,480.28
	SUBTOTAL IV - ELECTRICAL WORKS							4,231,749.05
	TOTAL DIRECT WORKS							
V	Service Fee							
4.1	DPL GAE 3%	lot	1.00				145,735.94	145,735.94
							TOTAL:	5,003,600.75

Prepared by:

JOHN KRISTIAN A. RAMOS
Project Engineer

PROJECT: **GATE & GUARDHOUSE**

LOCATION:

DATE:

SUBJECT: **BILL OF QUANTITIES**

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
GENERAL REQUIREMENTS								
Mobilization/Demobilization	lot	1.00				included in MRB		-
Bonds	lot	1.00					-	-
Temporary Facilities	lot	1.00				included in MRB		-
Temporary Power, Water & Communication	lot	1.00	2.30%			80,000.00	80,000.00	80,000.00
Office Equipment, Furnitures & Consumables	lot	1.00				included in Amenities		-
Construction Tools and Equipment	lot	1.00				included		-
Site Management Personnel	lot	1.00	5.43%		188,453.33		188,453.33	188,453.33
	lot	1.00	2.19%			76,103.83	76,103.83	76,103.83
Transportation	lot	1.00				included in MRB		-
Materials and Sampling	lot	1.00	0.49%			17,074.47	17,074.47	17,074.47
Hoarding Fence (for temfacil only)	lot	1.00				included in MRB		-
Housekeeping	lot	1.00				included in MRB		-
As Built Plans	lot	1.00	0.47%			16,431.91	16,431.91	16,431.91
Permits	lot	1.00					-	-
Construction Survey & Stake-Out	lot	1.00				included in MRB		-
SUBTOTAL I - GENERAL REQUIREMENTS			10.89%					378,063.55
STRUCTURAL WORKS								
All works shall be in accordance with the Drawings, Specifications and								
Tender Documents, all to the approval and acceptance of the Designer/Owner								
Site Works								
Safety (Security excluded, by FLI)	m2	792.77	0.57%	-	-	-	25.00	19,819.25
Excavation	m3	45.82	0.57%	-	-	430.00	430.00	19,703.50
Backfilling & Disposal	m3	36.52	0.33%		317.16		317.16	11,583.44
Gravel Bedding	m3	5.95	0.28%	1,479.79	158.26	-	1,638.05	9,741.63
Soil Treatment	m2	15.97	0.04%	86.33	4.42	-	90.75	1,449.25
Vapor Barrier; 0.15mm thick polyethylene film	m2	15.97	0.02%	44.87	8.59	-	53.46	853.77
Sub-total: Site Works			1.82%					63,150.85
Cast-in-Place Concrete								
Slab	m3	23.50	4.09%	5,165.00	870.13		6,035.13	141,843.05
Beams	m3	8.03	1.40%	5,165.00	870.13	-	6,035.13	48,440.41
Columns	m3	7.45	1.30%	5,165.00	870.13	-	6,035.13	44,973.82
Wall Footing	m3	2.00	0.35%	5,165.00	870.13	-	6,035.13	12,065.44
Column Footing	m3	3.93	0.68%	5,165.00	870.13	-	6,035.13	23,724.11
RC wall	m3	6.81	1.18%	5,165.00	870.13	-	6,035.13	41,090.22
Clearing and Grubbing	m3	0.15	0.03%	5,165.00	870.13	-	6,035.13	905.27
Canopy	m3	0.07	0.01%	5,165.00	870.13	-	6,035.13	407.37

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
Countertop	m3	0.08	0.01%	5,165.00	870.13	-	6,035.13	488.85
Pedestal for Access Barrier	m3	0.25	0.04%	5,165.00	870.13	-	6,035.13	1,520.85
Sub-total: Concrete			9.09%					315,459.39
Reinforcing Steel Bars								
Slab	kgs	2,326.79	3.46%	40.43	11.24	included	51.67	120,215.39
Beams	kgs	794.61	1.18%	40.43	11.24	included	51.67	41,054.41
Columns	kgs	737.75	1.10%	40.43	11.24	included	51.67	38,116.40
Wall Footing	kgs	197.92	0.29%	40.43	11.24	included	51.67	10,225.75
Column Footing	kgs	389.17	0.58%	40.43	11.24	included	51.67	20,106.76
RC wall	kgs	694.47	1.03%	40.43	11.24	included	51.67	35,880.25
Concrete Pavement	kgs	14.85	0.02%	40.43	11.24	included	51.67	767.24
Canopy	kgs	6.68	0.01%	40.43	11.24	included	51.67	345.26
Concrete Pavement	kgs	8.02	0.01%	40.43	11.24	included	51.67	414.31
Pedestal for Access Barrier	kgs	15.12	0.02%	40.43	11.24	included	51.67	781.19
Sub-total: Rebars			7.72%					267,906.94
Formworks								
Slab	m2	96.25	1.24%	309.92	116.88	21.34	448.14	43,134.70
Beams	m2	110.82	1.43%	309.92	116.88	21.34	448.14	49,664.18
Columns	m2	119.36	1.54%	309.92	116.88	21.34	448.14	53,489.95
Wall Footing	m2	10.00	0.13%	309.92	116.88	21.34	448.14	4,479.60
Column Footing	m2	11.43	0.15%	309.92	116.88	21.34	448.14	5,122.24
RC wall	m2	8.22	0.11%	309.92	116.88	21.34	448.14	3,682.36
Concrete Pavement	m2	0.45	0.01%	309.92	116.88	21.34	448.14	201.66
Canopy	m2	0.95	0.01%	309.92	116.88	21.34	448.14	423.49
Countertop	m2	1.01	0.01%	309.92	116.88	21.34	448.14	450.38
Pedestal for Access Barrier	m2	1.68	0.02%	309.92	116.88	21.34	448.14	752.87
Countertop								
Sub-total: Formworks			4.65%					161,401.44
SUBTOTAL II - STRUCTURAL WORKS			23.27%					807,918.62
ARCHITECTURAL WORKS								
Concrete								
Concrete Topping	m2	105.07	0.58%	100.00	92.73	-	192.73	20,250.14
25x25mm G.A # 16 G.I. Wire Mesh Reinforcement	m2	2.37	0.03%	225.00	171.97	-	396.97	939.23
75x150mm pre-cast concrete with smooth paint finish (1.1m high)	pcs	41.00	1.00%	618.75	229.50	-	848.25	34,778.44
Sub-total: Concrete Works			1.61%					55,967.81
Masonry Works								
100mm thk CHB wall	m2	115.54	2.43%	455.87	232.21	41.13	729.21	84,253.94
	m2	130.56	3.41%	528.51	322.64	54.89	906.04	118,294.40
Plastering	m2	500.59	4.80%	154.81	178.04	-	332.85	166,619.98
Sub-total: Masonry Works			10.63%					369,168.31

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
Metal Works								
50x100x1.5mm thk hot dipped g.s. tubular frame with smooth spary paint finish	lm	48.00	0.62%	373.13	50.57	21.70	445.40	21,379.07
38x38x1.2mm thk hot dipped g.s. tubular vertical rail with smooth spray paint finish	lm	96.00	0.47%	100.42	39.20	28.55	168.17	16,144.06
Heavy duty bearing type pillow block hinge	pc/s	8.00	0.11%	340.00	102.00	34.00	476.00	3,808.00
U-channel guide rail	lm	13.00	0.59%	1,172.66	309.06	103.02	1,584.73	20,601.48
50x100x1.2mm thk hot-dipped g.s. tubular lattice with smooth spray paint finish (2.5m high)								
to lattice	lm	42.00	0.54%	373.13	50.57	21.70	445.40	18,706.69
Access Barrier								
to barrier (3.75m)	pc/s	2.00	6.40%				111,170.21	222,340.43
Sub-total: Metal Works			8.73%					302,979.73
150mm thk CHB wall								
Wood and Plastic								
ID rack ; 19mm thk K.D treated plyboard with 6mm thk K.D treated Tanguile solid wood edging,smooth painted	lot	1.00	0.12%	3,475.27	833.14		4,308.41	4,308.41
Sub-total: Wood and Plastic			0.12%					4,308.41
Thermal & Moisture Protection								
Liquid PU Membrane Waterproofing								
to roof slab	m2	104.31	3.52%	739.89	432.74	-	1,172.63	122,316.92
to water feature	m2	69.59	2.35%	739.89	432.74	-	1,172.63	81,600.90
Sub-total: Thermal and Moisture Protection			5.87%					203,917.82
Doors and Windows								
Wooden Doors								
D1 600 x 2100	set/s	1.00	0.26%	8,099.12	606.81	386.10	9,092.02	9,092.02
Sub-total: Doors and Door Jambs			0.26%					9,092.02
Door Hardwares								
Hinges								
3pcs 3-1/2" x 3-1/2" x 3mm thk stainless steel (ASTM 304) 2-ball bearing loose pin hinges	pcs	3.00	0.02%	170.74	23.43	-	194.18	582.53
Lockset	set	1.00	0.02%	569.15	192.05		761.19	761.19
Sub-total: Door Hardwares			0.04%					1,343.72
Glass Windows								
W-1 1490 x 1500	set/s	1.00	0.32%	9,258.49	1,336.19	520.92	11,115.59	11,115.59
6mm thk clear glass frameless fixed window								
W-2 800 x 600	set/s	1.00	0.07%	1,988.40	268.92	111.88	2,369.19	2,369.19
6mm thk clear glass sliding on powder coated aluminum frame								
40mm thk flush type hollow core treated kiln dried 'tanguile' with 6mm thk marine plywood on both sides & qde paint finish	set/s	1.00	0.27%	7,953.60	1,075.68	447.50	9,476.77	9,476.77
6mm thk clear glass frameless fixed window								
W-4 2510 x 1200	set/s	1.00	0.43%	12,477.21	1,687.47	702.02	14,866.69	14,866.69
6mm thk clear glass frameless fixed window								
W-5 1290 x 1200	set/s	1.00	0.22%	6,412.59	867.26	360.80	7,640.65	7,640.65
6mm thk clear glass frameless fixed window								

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
W-6 2100 x 1200	set/s	1.00	0.36%	10,439.10	1,411.82	587.34	12,438.27	12,438.27
6mm thk clear glass frameless fixed window								
Sub-total: Windows			1.67%					57,907.17
FINISHES								
WALL FINISHES								
Smooth Paint Finish								
to wall	m2	465.29	6.21%	227.66	235.60	-	463.26	215,550.28
to plant box	m2	6.48	0.09%	227.66	235.60	-	463.26	3,002.15
W-3 1600 x 1200	m2	14.32	0.19%	227.66	235.60	-	463.26	6,632.72
to canopy	m2	0.97	0.01%	227.66	235.60	-	463.26	449.36
to lattice	m2	7.28	0.10%	227.66	235.60	-	463.26	3,372.53
to fence	m2	13.53	0.18%	227.66	235.60	-	463.26	6,267.90
to ID rack	m2	0.80	0.01%	227.66	235.60	-	463.26	370.61
to cabinet	m2	0.32	0.00%	227.66	235.60	-	463.26	148.24
		508.99						
300x300mm vitrified unglazed ceramic tiles								
to toilet	m2	5.27	0.12%	355.15	324.67	138.50	818.32	4,315.84
200x1200mm simulated wood porcelain tile finish								
to brand marker	m2	12.84	0.32%	612.50	183.75	61.25	857.50	11,010.30
to project marker	m2	22.68	0.56%	612.50	183.75	61.25	857.50	19,448.10
Artificial Green Wall								
to gate	m2	6.75	1.41%	-	-	-	7,231.83	48,814.88
to decorative post								
Artificial stone wall cladding								
to guard station	m2	10.79	0.67%	1,707.45	324.67	138.50	2,170.62	23,421.02
to water feature	m2	3.65	0.23%	1,707.45	324.67	138.50	2,170.62	7,922.77
FLOOR FINISHES								
300x300mm vitrified unglazed ceramic tiles								
to guard station	m2	5.79	0.14%	355.15	324.67	138.50	818.32	4,738.10
to toilet	m2	1.97	0.05%	355.15	324.67	138.50	818.32	1,612.10
600x600mm glazed ceramic tile								
to countertop	m2	0.74	0.03%	641.65	317.33	224.00	1,182.98	875.41
150x150mm outdoor type 'granito' tiles								
to driveway	m2	143.68	4.61%	649.69	324.67	138.50	1,112.86	159,896.17
to water feature	m2	69.59	1.92%	495.00	324.67	138.50	958.18	66,677.52
CEILING FINISHES								
4.0mm thk Fiber cement ceiling board with paint finish on suspended metal furring framing								
to ceiling	m2	93.40	2.32%	531.91	328.83	-	860.74	80,393.22
exposed off-form slab/ canopy soffit with smooth paint finish								
to ceiling	m2	8.85	0.12%	227.66	235.60	-	463.26	4,099.85

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
Sub-total: Finishes			19.27%					669,019.07
SPECIALTIES								
Plumbing Fixtures								
Toilet Fixtures and Accessories								
300x300mm blue glass mosaic tile finish	pc/s	1.00	0.05%	1,614.89	-	-	1,614.89	1,614.89
Water closet	pc/s	1.00	0.25%	5,920.00	2,701.55	-	8,621.55	8,621.55
Lavatory faucet	pc/s	1.00	0.25%	5,920.00	2,701.55	-	8,621.55	8,621.55
Kitchen Sink & Faucet	pc/s	1.00	0.07%	1,942.29	563.08	-	2,505.37	2,505.37
Signages								
to brand marker "ASPIRE BY FILINVEST"	lot	1.00	2.28%	79,111.70	included	included	79,111.70	79,111.70
to project marker "MALDIVES OASIS DAVAO"	lot	1.00	2.02%	70,119.15	included	included	70,119.15	70,119.15
Sub-total: Specialties			4.91%					170,594.21
SUBTOTAL III - ARCHITECTURAL WORKS			53.13%					1,844,298.29
PLUMBING & SANITARY WORKS								
DRAINAGE SYSTEM								
Lavatory								
150mmØ	lm	19.00	0.48%	639.12	148.92	80.42	868.45	16,500.58
100mmØ	lm	4.00	0.04%	248.20	69.50	37.53	355.22	1,420.90
75mmØ	lm	28.50	0.22%	186.39	52.17	28.17	266.74	7,601.98
50mmØ	lm	9.00	0.03%	96.85	24.33	13.14	134.32	1,208.88
Fittings:								
Coupling								
150mmØ	pc/s	3.00	0.06%	446.76	156.37	48.25	651.38	1,954.13
100mmØ	pc/s	1.00	0.00%	79.42	27.80	8.58	115.80	115.80
75mmØ	pc/s	3.00	0.00%	37.00	7.40	2.22	46.62	139.86
Wye / Wye Reducer								
100 x 75mmØ	pc/s	2.00	0.02%	252.58	88.40	27.28	368.26	736.52
75 x 75mmØ	pc/s	1.00	0.00%	100.68	35.24	10.87	146.80	146.80
Elbow 45°								
50mmØ	pc/s	5.00	0.01%	31.68	11.09	3.42	46.19	230.96
PVC Pipe, Series 1000								
75mmØ	pc/s	15.00	0.05%	79.42	27.80	8.58	115.80	1,736.99
50mmØ	pc/s	2.00	0.00%	39.71	13.90	4.29	57.90	115.80
Deck Drain								
75mmØ	pc/s	5.00	0.34%	1,886.80	377.36	113.21	2,377.37	11,886.84
50mmØ	pc/s	2.00	0.12%	1,670.00	334.00	100.20	2,104.20	4,208.40
Catch Basin	pc/s	2.00	0.79%	9,455.88	3,309.56	1,021.23	13,786.67	27,573.33
Sub-total			2.18%					75,577.77
SEWER & VENT LINE								
PVC Pipe, Series 1000								
100mmØ	lm	14.50	0.15%	248.20	69.50	37.53	355.22	5,150.75
50mmØ	lm	2.00	0.01%	96.85	24.33	13.14	134.32	268.64

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
Fittings:								
Elbow 90°								
100mmØ	pc/s	2.00	0.01%	79.42	27.80	8.58	115.80	231.60
50mmØ	pc/s	1.00	0.00%	18.00	3.60	1.08	22.68	22.68
Wye / Wye Reducer								
100 x 100mmØ	pc/s	1.00	0.01%	131.00	45.85	14.15	191.00	191.00
100 x 50mmØ	pc/s	2.00	0.01%	159.14	55.70	17.19	232.03	464.05
Elbow 90°								
100mmØ	pc/s	1.00	0.01%	143.85	50.35	15.54	209.73	209.73
P-Trap								
50mmØ	pc/s	1.00	0.01%	123.08	43.08	13.29	179.45	179.45
Clean out								
100mmØ	pc/s	1.00	0.00%	97.40	34.09	10.52	142.00	142.00
Septic Tank : volume: 1 cu. Meter, KOTEC or Approved Equal	pc/s	1.00	0.18%	5,720.00	489.70	30.00	6,239.70	6,239.70
Sub-total			0.38%					13,099.60
Coupling								
PLUMBING FIXTURE								
Water Closet	set/s	1.00	0.03%	c/o Archi	665.49	387.50	1,052.99	1,052.99
Lavatory w/ Faucet	set/s	1.00	0.02%	c/o Archi	443.66	156.25	599.91	599.91
Floor Drain (Stainless Steel)	pc/s	1.00	0.01%	250.00	86.65	112.50	449.15	449.15
Sub-total			0.06%					2,102.06
WATER LINE								
PPR Pipe								
20mmØ	lm	5.20	0.04%	192.38	67.33	20.78	280.48	1,458.52
PPR Fittings:								
Coupling								
20mmØ	pc/s	1.00	0.00%	40.88	14.31	4.42	59.60	59.60
Elbow 90° (Plain)								
	pc/s	2.00	0.00%	59.29	20.75	6.40	86.44	172.88
Threaded Elbow (Female)								
20mmØ	pc/s	2.00	0.03%	394.20	78.84	23.65	496.69	993.38
Tee								
20mmØ	pc/s	2.00	0.01%	61.32	21.46	6.62	89.40	178.81
Male Threaded Adaptor								
20mmØ	pc/s	2.00	0.04%	449.68	157.39	48.57	655.63	1,311.27
Gate Valve								
20mmØ	pc/s	1.00	0.09%	2,246.15	786.15	242.58	3,274.89	3,274.89
Hose Bibb								
20mmØ	pc/s	1.00	0.03%	790.22	276.58	85.34	1,152.13	1,152.13
Water Meter Assembly								
Water Meter								
25mmØ	pc/s	1.00	0.04%	1,288.00	122.43	30.00	1,440.43	1,440.43
G.I Union Patente Sch. 40								
20mmØ	pc/s	2.00	0.01%	64.50	4.21	30.00	98.71	197.41

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
G.I Nipple Sch. 40								
25mmØ x 200mm	pc/s	2.00	0.01%	150.00	4.21	30.00	184.21	368.41
25mmØ x 75mm	pc/s	2.00	0.01%	75.00	4.21	30.00	109.21	218.41
G.I Elbow Sch. 40								
25mmØ	pc/s	2.00	0.00%	52.00	4.21	15.00	71.21	142.41
G.I Female Threaded Elbow Sch. 40								
25mmØ	pc/s	1.00	0.00%	52.00	4.21	15.00	71.21	71.21
PPR Threaded Elbow (Female)								
25mmØ	pc/s	1.00	0.00%	16.80	1.40	1.92	20.12	20.12
Winged Lock / Valve								
20mmØ	pc/s	1.00	0.01%	180.00	4.21	7.50	191.71	191.71
Sub-total			0.32%					11,251.59
SUBTOTAL IV - PLUMBING WORKS			2.94%					102,031.01
25mmØ								
ELECTRICAL WORKS								
LIGHTING & POWER SYSTEM (Guard House)								
Roughing Ins PVC								
20 mm ø PVC x 3m	pc/s	59.00	0.20%	72.00	21.60	21.94	115.54	6,816.65
20 mm ø PVC Coupling	pc/s	29.50	0.01%	5.63	1.41	0.34	7.37	217.38
20 mm ø Male adapter	pc/s	94.00	0.01%	4.36	0.53	0.27	5.16	484.68
15 mm ø IMC Locknut and Bushing	pc/s	94.00	0.02%	6.43	2.06		8.49	797.96
15mmØ FMC	lm	38.00	0.03%	25.75	3.12	-	28.87	1,097.06
15mmØ Straigh Connector	pc/s	38.00	0.03%	21.70	1.88	-	23.58	895.98
Wires & Cables								
3.5mm2 THW	lm	193.60	0.17%	22.11	6.63	2.53	31.27	6,053.48
Lighting Fixtures								
15W, LED Luminare, Warm White Complete Housing, Square Pinlight	set/s	24.00	0.72%	840.00	184.80	16.80	1,041.60	24,998.40
	set/s	2.00	0.13%	1,784.85	446.21	35.70	2,266.76	4,533.52
Wall bracket lamps 40W, LED lamp, Weathre Proof Decorated Die Cast, Aluminum Housing and gasketed Housing	set/s	6.00	0.19%	892.43	196.33	17.85	1,106.61	6,639.64
Wiring Device								
1 Gang Switch	set/s	2.00	0.01%	118.50	26.06	-	144.56	289.11
2 Gang Switch	set/s			129.49	32.37	-	161.87	-
3 Gang Switch	set/s	3.00	0.02%	139.05	38.93	-	177.98	533.95
Duplex Outlet	set/s	2.00	0.02%	248.23	69.50	-	317.73	635.47
Boxes and Pull Boxes								
Square Box	pc/s	2.00	0.00%	56.25	6.75	1.06	64.06	128.13
Junction Box	pc/s	38.00	0.06%	49.44	5.93	1.06	56.44	2,144.57
Utility Box	pc/s	7.00	0.01%	37.08	4.45	1.06	42.59	298.15
Others								
Testing & Commissioning	lot	1.00	0.06%		2,024.42		2,024.42	2,024.42
120W Wall Mounted Spotlight			1.69%					58,588.56
Panel Board								

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
LPG Main; 100AT/100AF, 2PMCB, 230V, 60Hz.,10Kaic Branches: 1-60AT/100AF, B.O 5-20AT/50AF, BO 1-30AT/50AF, Spare, BO 1-20AT/50AF, Spare, BO Enclosure: Nema I Mounting: Semi Recessed	assy.	1.00	0.38%	10,450.73	2,612.68	209.01	13,272.43	13,272.43
Others								
Testing & Commissioning	lot	1.00	0.02%		653.17		653.17	653.17
Sub-total - Panel Board			0.40%					13,925.60
Telephone System								
Roughing Ins PVC								
25 mm ø PVC x 3m	pc/s	27.00	0.12%	109.00	24.02	21.94	154.96	4,183.81
25 mm ø PVC Coupling	pc/s	13.50	0.00%	8.63	2.16	0.43	11.21	151.37
25 mm ø Male adapter	pc/s	6.00	0.00%	6.40	0.50	0.33	7.23	43.40
20 mm ø IMC Locknut and Bushing	pc/s	6.00	0.01%	39.50	3.06		42.56	255.38
Wires and Cables								
# 22/4C Telephone Jacketed Cable	lm	89.10	0.06%	17.00	5.10	1.63	23.72	2,113.85
Sub-total -Lighting and Power								
Wiring Devices								
Tel. Outlet	set/s	1.00	0.01%	289.43	86.83	-	376.26	376.26
Box and Pull Boxes								
Utility Box	pc/s	1.00	0.00%	37.08	4.45	1.06	42.59	42.59
Others								
Sub-Total Telephone System			0.21%					7,166.67
CCTV System								
Roughing Ins IMC								
25 mm ø PVC x 3m	pc/s	5.00	0.02%	109.00	24.02	21.94	154.96	774.78
25 mm ø PVC Coupling	pc/s	2.50	0.00%	8.63	2.16	0.43	11.21	28.03
25 mm ø Male adapter	pc/s	4.00	0.00%	6.40	0.50	0.33	7.23	28.93
20 mm ø IMC Locknut and Bushing	pc/s	4.00	0.00%	39.50	3.06		42.56	170.26
Cat 5e UTP Cable	lm	16.50	0.01%	26.68	3.67	0.38	30.73	507.04
Fixtures and Equipment								
Bullet IR Type, Outdoor, Fixed, 3.0-12mm Lens, 720P	set/s	2.00	0.15%	2,275.46	318.30	31.32	2,625.08	5,250.17
Digital Video Recorder, Stand Alone, 3TB, Hard Disk 1920 x 1080, HDMI, H264 Video, Compression Channel 4/8/16/32	set/s	1.00	0.11%	3,413.76	526.33	1.55	3,941.63	3,941.63
UPS, 500VA	set/s	1.00	0.07%	1,878.19	300.76	126.40	2,305.35	2,305.35
Boxes and Pull Boxes								
Juction Box uPVC	pc/s	4.00	0.01%	49.44	5.93	1.06	56.44	225.74
Others								

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
Testing & Commissioning	lot	1.00	0.01%		381.04		381.04	381.04
Sub-total - CCTV System			0.39%					13,612.97
Wires and Cables								
SUBTOTAL V - ELECTRICAL WORKS (GUARDHOUSE)			2.69%					93,293.80
LIGHTING & POWER SYSTEM (Landscape)								
Roughing Ins PVC								
25 mm ø PVC x 3m	pc/s	107.00	0.48%	109.00	24.02	21.94	154.96	16,580.29
25 mm ø PVC Coupling	pc/s	53.50	0.02%	8.63	2.16	0.43	11.21	599.87
25 mm ø Male adapter	pc/s	18.00	0.00%	6.40	0.50	0.33	7.23	130.20
20 mm ø IMC Locknut and Bushing	pc/s	18.00	0.02%	39.50	3.06		42.56	766.15
Wires & Cables								
3.5mm2 TW	lm	234.30	0.21%	22.11	6.63	2.53	31.27	7,326.09
5.5mm2 THW	lm	468.60	0.57%	33.84	5.84	2.53	42.20	19,775.18
Lighting Fixtures								
70W High Pressure Sodium Lamp	set/s	3.00	0.30%	2,800.00	616.00	6.82	3,422.82	10,268.46
50W Metal Halide Flood Light	set/s	2.00	0.17%	2,450.00	448.89	3.50	2,902.39	5,804.79
	set/s	6.00	0.19%	892.43	196.33	17.85	1,106.61	6,639.64
Boxes and Pull Boxes								
Square Box	pc/s	4.00	0.01%	56.25	6.75	1.06	64.06	256.25
Others								
Lamp Pole 3M	pc/s	3.00	0.89%	7,850.00	1,256.00	1,200.00	10,306.00	30,918.00
Testing & Commissioning	lot	1.00	0.06%	-	2,053.69	-	2,053.69	2,053.69
Sub-total -Lighting and Power			2.91%					101,118.61
Service Entrance, Feeders and Sub Feeders								
Roughing Ins RSC								
20 mm ø RSC x 3m	pc/s	2.00	0.03%	365.00	78.83	24.47	468.30	936.60
20 mm ø Service Entrance Cap	pc/s	1.00	0.00%	104.50	7.97		112.47	112.47
Wall bracket lamps 40W, LED lamp, Weathre Proof Decorated Die Cast, Aluminum Housing and gasketed Housing								
25mm PVC pipes x 3m	pc/s	23.00	0.10%	109.00	24.02	21.94	154.96	3,563.99
25 mm ø PVC Coupling	pc/s	11.50	0.00%	8.63	2.16	0.43	11.21	128.94
25mm PVC male adapter	pc/s	6.00	0.00%	6.40	0.50	0.33	7.23	43.40
20 mm ø IMC Locknut and Bushing	pc/s	6.00	0.01%	39.50	3.06		42.56	255.38
32mm PVC pipes x 3m	pc/s	13.00	0.07%	143.00	31.60	21.94	196.54	2,555.03
32 mm ø PVC Coupling	pc/s	6.50	0.00%	14.63	3.66	0.56	18.84	122.45
32 mm ø Adapter	pc/s	6.00	0.00%	10.20	0.86	0.02	11.08	66.45
25 mm ø IMC Locknut and Bushing	pc/s	6.00	0.01%	40.75	4.89		45.64	273.84
Wires & Cables								
8.0mm2 THW	lm	149.60	0.32%	60.30	9.35	4.50	74.15	11,093.59
8.0mm2 TW	lm	74.80	0.16%	60.30	9.35	4.50	74.15	5,546.79
Others								
Electric Meter Base	set/s	1.00	0.07%	1,950.00	570.00	39.00	2,559.00	2,559.00
Concrete Pedestal 300mm x 300mm	pc/s	1.00	0.07%	2,219.68	313.29	9.80	2,542.77	2,542.77

DESCRIPTION	UNIT	QTY	WEIGHT	UNIT COST				AMOUNT
				MATERIAL	LABOR	OTHERS	TOTAL	
Roughing Ins PVC	pc/s	2.00	0.33%	4,500.00	1,125.00	90.00	5,715.00	11,430.00
Ground Rod	pc/s	1.00	0.06%	1,462.50	157.30	331.00	1,950.80	1,950.80
Testing & Commissioning	lot	1.00	0.01%	-	349.88	-	349.88	349.88
Sub-Total Service Entrance, Feeders and Sub Feeders			1.25%					43,531.38
SUBTOTAL VI - LIGHTING & POWER SYSTEM (LANDSCAPE)			4.17%					144,649.99
TOTAL DIRECT WORKS			86.20%					2,992,191.72
SERVICE FEE								
DPI GAE	lot	1.00	2.91%				101,107.66	101,107.66
SUBTOTAL VII - SERVICE FEE			2.91%					101,107.66
TOTAL CONSTRUCTION COST (Gate & Guardhouse)								3,471,362.92

Prepared by:

JOHN KRISTIAN A. RAMOS
Project Engineer